Bradford Reclamation District 2059

Board of Trustees:
President: Robert Davies
Trustees: William Hall,
Kevin Finta, Jaime Eddy, vacant
www.bradfordisland.com

November 9, 2026

All Bidders that attended mandator Pre-bid for the Levee Crown Rehabilitation Project

RE: Bradford Reclamation District 2059 Levee Crown Rehabilitation Project Questions/Answers

1. Would recycled Base Rock be allowed on the Project ? *Yes, recycled base rock may be used. Must meet Caltrans spec for recycled ¾" Class II aggregate base:* ***30-1.02B Supplementary Aggregate*** *- If supplementary aggregate is specified, supplementary aggregate must comply with 3/4 inch maximum gradation specified in section 26-1.02. Supplementary aggregate must not include cinders. Do not use supplementary aggregate with more than 50 percent by volume of recycled asphalt concrete. Supplementary aggregate must weigh at least 105 lb/cu ft, determined under California Test 212, Compacted Method (by Rodding).*

2. Can we get a total lineal foot of Levee crown to be prepared & AB to be placed? *A total lineal footage has not been computed. Bid is based on total tonnage placed. Once bids have been received and a contractor selected, the footage will be computed.*

3. Can haul trucks be left on Island? *Yes, haul trucks can be left on the island.*

Phone: 925-209-5480 Email: bradford2059@gmail.com
Mailing Address: PO Box 1059 Oakley, CA 94561
Shipping Address: 6329 Bethel Island, Ste A Bethel Island, CA 94511
(Contra Costa County)